No.	Items of work	Unit	Sanctioned		Rate quoted in	
			Quantity	Rate	Figures	Words
				Rs. a. p.		
	Sluice at R. L. 44·00.					
1	Earthwork, cut opening the bund and forming a ring bund in front ..	C.yd.	249	0 3 0		
2	Burnt stone jelly concrete in surki mortar	C.ft.	234	0 3 9		
3	Burnt brick in surki mortar ..	,,	506	0 4 6		
4	Burnt stone slabs 6″ thick, one line dressed and fixed in surki mortar	S.ft.	178	0 6 0		
5	Providing and fixing jallywood plug and L iron rod 2″×⅜″ in section with locking arrangements, etc., complete ..	Each	1	20 0 0		
6	Cutting holes in slab ..	,,	4	1 0 0		
7	Plastering with surki mortar ..	Sqr.	6.86	3 4 0		
8	Refilling the cut earth including consolidation ..	C.yd.	249	0 4 0		
9	Gravel backing	C.yd.	40	0 8 0		
10	Removing and resetting old stone work with new jelly backing and jelly wedging	,,	18	1 0 0		
11	Providing, laying and jointing with cement 9″ Dr. C. I. Bhadravati pipes (Pipes will be supplied Departmentally)	R.ft.	48	2 8 0		
	Restoring silt drains 1, 2 & 3.					
1	Earthwork, removing silt and sand ..	C.yd.	528	0 2 3		
2	Earthwork to bund of feeder with watering and tamping ..	,,	1,152	0 4 0		
3	Rough stone work new with the required lead and lift with jelly backing and jelly wedging ..	,,	221	1 8 0		
4	Puddle mixed with clay and gravel in equal proportion for the breach ..	,,	47	0 8 0		
5	Turfing and watering till it is satisfactory	S.yd.	483	0 1 0		
6	Earthwork excavation ..	C.yd.	8	0 4 0		
7	Burnt brick in surki mortar ..	C.ft.	242	0 4 6		
8	Burnt stone slabs 6″ thick, one line dressed and fixed in surki mortar ..	S.ft.	77	0 6 0		
9	Plastering with surki mortar ..	Sqr.	3.00	3 4 0		
10	Benching rock ..	S.ft.	20	0 4 0		
11	Providing joggle joints ..	Each	7	1 0 0		
12	Earthwork done at the relieving weirs will be used for the bund and payment will be made under Bund of feeder channel ..	..	..	..		

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Abstract Notification dated the 5th February 1938.

The attention of the public is invited to the Notification published in pages 198-202, Part VI of the *Mysore Gazette*, dated the 10th February 1938, calling for sealed tenders for the construction of Krishnarajendra Police Station at Mysore.

The earnest money to be deposited along with the tender is Rs. 380.
The last date for receiving tenders is 26th February 1938, before 3 P.M.

M. A. RAMANUJAM,
Assistant Engineer.

HASSAN DIVISION.

Abstract Notification dated the 6th February 1938.

The attention of the public is invited to the Notification published in *Mysore Gazette* dated 10th February 1938, *vide* pages 202-204, Part VI, calling for tenders for "Constructing first floor to the Administrative Block of Sri Chamarajendra Hospital at Hassan". The last date for receipt of tenders is 26th February 1938.

D. A. HUKERI,
Executive Engineer.

KADUR DIVISION.

Notification dated 19th February 1938.

Sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, Chikmagalur, up to 3 P.M. on 14th March 1938, for constructing a Bridge across Herur Halla at 2/1 of Herur-Basarikatte Road.

2. Tenders in the prescribed form obtainable in the Office of the Executive Engineer, Kadur Division, Chikmagalur, should be addressed to the Executive Engineer, Kadur Division, Chikmagalur, and should be superscribed as "Tender for constructing a Bridge across Herur Halla at 2/1 of Herur-Basarikatte Road." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender should be accompanied by a deposit of Rs. 335 only in cash as earnest money. The earnest money of the successful tenderer will be retained as cash security for the due fulfilment of the contract. Cash amount will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on the date at the time of opening. The final acceptance of the tender will rest with the Executive Engineer, Kadur, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Office of the Executive Engineer in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings may be seen at any time at the Office of the Executive Engineer, Kadur Division, Chikmagalur, on all working days between 11 A.M. and 5 P.M.

8. Specific rates should be given for each item in the schedule and the rates should be in rupees, annas and pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney authorising him to do so.

14. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Executive Engineer, Kadur Division, and approved by the Superintending Engineer, shall be final and legally binding on the tenderer.

15. The quantities in estimate are only approximate and are liable to alteration, omissions, deductions or additions, at the discretion of the Executive Engineer, Kadur Division, or his representative. The tendered rates will hold good for any quantity whether it is higher or lower than those estimated for.